



MOJAVE DESERT AIR QUALITY MANAGEMENT DISTRICT

14306 Park Avenue Victorville, CA 92392-2310
760.245.1661 -- 800.635.4617 -- FAX 760.245.2022

INACTIVE

C012847

Inactive type Permit has no description information.

EXPIRES LAST DAY OF: JUNE 2020

OWNER OF OPERATOR (Co.#2026)

GAMA Contracting Sevices, Inc.
District Wide
MDAQMD, CA 92392

EQUIPMENT LOCATION (Fac.#3335)

GAMA Contracting Sevices, Inc.
District Wide
MDAQMD, CA 92392

Description:

NEGATIVE AIR MACHINE consisting of: A Syclone Negative Air Machine, Serial No. 16GSY724, equipped with three stage filtration consisting of; pre-filter pad 24" x 24" x 1/2", ring panel filter 24" x 24" x 1/2", and HEPA filter 24" x 24" x 11 1/2", UL 900 Certified, 99.97% efficiency (at 0.3 microns) and having a two speed 1.0 hp motor, 1,175 or 2,000 cfm.

CONDITIONS:

1. This equipment shall be installed, operated and maintained in strict accordance with those recommendations of the manufacturer/supplier and/or sound engineering principles which produce the minimum emissions of contaminants. Unless otherwise noted, this equipment shall also be operated in accordance with all data and specifications submitted with the application for this permit. [District Rule 1320]
2. After each abatement use, this equipment must be emptied and cleaned within a negative air enclosure, and filters and waste collected with this equipment must be disposed as friable asbestos waste. [District Rule 1320; 40 CFR 61, Subpart M]
3. The HEPA filters used in the Negative Air Machine shall be certified by the manufacturer to have a minimum control efficiency of 99.97% on 0.3 micron particles. [District Rules 204 and 1320; 40 CFR 61.152(b)(2)]
4. During full containment projects, view ports shall be provided for inspection purposes. The view port dimensions shall be at least 18 inches square and the bottom of said port no less than 3 to 4 feet from the floor level.

Fee Schedule: 7 (h)

Rating: 1 device

SIC: 1795

SCC: 50300901

Location/UTM(Km):
704E/3717N

This permit does not authorize the emission of air contaminants in excess of those allowed by law, including Division 26 of the Health and Safety Code of the State of California and the Rules and Regulations of the District. This permit cannot be construed as permission to violate existing laws, ordinances, statutes or regulations of this or other governmental agencies. This permit must be renewed by the expiration date above. If billing for renewal fee required by Rule 301(c) is not received by expiration date above, please contact the District.

GAMA Contracting Sevices, Inc.
1835 Floradale Avenue
South El Monte, CA 91733

By: **COPY**
Eldon Heaston
Air Pollution Control Officer

[District Rule 204]

5. Viewing ports shall be sufficient in number to allow observation of all stripping and removal operations.

[District Rule 204]

6. A mechanical gauge shall be installed so as to indicate, in inches of water column, the pressure differential between the containment and the outside. The mechanical gauge shall be located in a manner that will allow an observer to easily monitor the differential pressure from outside the containment.

[District Rule 204; OSHA 29 CFR 1926.1101]

7. Owner/operator shall maintain negative pressure of 0.02 inches of water gauge minimum in the work area to prevent contaminants from escaping the containment barriers and to ensure that the negative air machine airflow is adequate.

[OSHA 29 CFR 1926.1101]

8. The hours of operation of this device shall not exceed 1500 hours per year when operated at any single demolition or renovation site (site). The combined operating hours of all co-located negative air machines shall not exceed 3000 hours per year at any single site.

[District Rule 1520]

9. The negative air machine shall be tested and checked for leakage and rupture after each HEPA filter change and prior to commencement of any abatement project. Filters should be checked and changed in accordance with the manufacturer's recommendations, but not to exceed the following intervals:

a. HEPA filter must be replaced when the pressure differential gauge reads between 2.2" and 2.5" at high speed with clean prefilters, or every 1800 hours of use, whichever occurs first.

[District Rules 1302 and 1320; Manufacturer's Maintenance Manual]

10. A pressure gauge shall be installed and maintained on the negative air machine to indicate, in inches of water column, the pressure differential across the HEPA filter. The pressure differential across the filter shall be recorded at the beginning of each day of use and immediately after any filter change. The pressure differential shall be checked periodically and the pressure differential shall not be less than the initial reading (reading at the beginning of each day of use or reading after any filter change). In the event that the pressure differential is less than the initial reading, the negative air machine shall be turned off and shall be checked for leakage and rupture of the HEPA filter.

[District Rules 1302 and 1320; Manufacturer's Maintenance Manual]

11. The owner/operator shall keep adequate records for this negative air machine to verify:

a. The number of working hours per day involving asbestos removal for this machine;

b. The pressure gauge reading at the beginning of each day of use and after each change of HEPA filter, including the time and date of the reading;

c. A copy of the manufacturer's certification of efficiency for the HEPA filters;

d. The date, time, and type of each filter replacement; and

e. The date and time of each machine addition/replacement.

These records shall be maintained for a period of two (2) years and made available to District personnel upon request.

[District Rules 1302 and 1320]

12. This unit may, at the discretion of the owner/operator, be used on any commercial asbestos abatement project for a demolition or renovation pursuant to 40 CFR 61, Subpart M - National Emission Standard for Asbestos if the project is properly notified to the District. Proper notification must be consistent with 40 CFR 61, Subpart M, a minimum of ten (10) working days prior to commencement and sent to asbestos@mdaqmd.ca.gov.

[40 CFR 61, Subpart M]

13. Any project containing Regulated Asbestos Containing Material (RACM) shall have onsite at least one trained operator as specified in 40 CFR 61.145(c)(8) during the removal of RACM. Evidence of training shall be presented to District personnel upon request.

[40 CFR 61, Subpart M]

14. This equipment and all operations pertaining to the use of this equipment are subject to the requirements of the National Emission Standard for Hazardous Air Pollutants, Subpart M - NESHAP for Asbestos (40 CFR 61, Subpart M).

15. The Executive Officer or his representative shall be notified and a written approval shall be obtained prior to commencement of any abatement project is located within 1,000 feet from the outer boundary of a school.
[H&SC 42301.6]

16. A facility wide Comprehensive Emission Inventory (CEI) for all emitted criteria and toxic air pollutants must be submitted to the District, in a format approved by the District, upon District request.
[District Rule 107(b), H&S Code 39607 & 44341-44342, and 40 CFR 51, Subpart A]